

BOQ FOR PROPOSED DATA-CABLING WORK FOR CENTRAL BANK OF INDIA NEW PREMISES Mylapore Branch

DATA CABLING WORK

Sl. No	Description of Work	Qty	Unit
1	Supply and laying of E CAT6 Network cable in the Aluminum trunking box.	200	P/Mtr
2	Supply and fixing of RJ45 Network socket with front plate and base box for computer workstations.(DOUBLE OUTPUT)	13	P/No
3	Supply and fixing of 3 feet patch card (Systimax)	13	P/No
4	Supply and fixing of 7 feet patch card (Systimax)	13	P/No
5	Supply and fixing of 24 port switch. (Cisco make)	1	P/No
6	Refixing of 24 port jack panel (Systimax make)	1	P/No
7	Refixing of wall mountable Rack 12Uwith power adaptor etc.	1	P/No
	Total		

GST 18%

Total