

BOQ FOR PROPOSED AC WORK FOR CENTRAL BANK OF INDIA NEW PREMISES FOR Mylapore Branch**AIRCONDITIONING WORK**

Sl.No	Description Of Work	Qty	Unit
A	BANKING HALL/ BRANCH MANAGER CABIN		
1	Supply & installation of 1.5TR capacity high wall split air-conditioner (5 star rated) including 4mts length copper and drain piping and 5KVA voltage stabilizer, installation of outdoor units including stand, civil works complete.	2	1 No
1	Supply & installation of 2.0TR capacity high wall split air-conditioner (5 star rated) including 4mts length copper and drain piping and 5KVA voltage stabilizer, installation of outdoor units including stand, civil works complete.	4	1 No
2	Power cable outdoor to indoor	40	1Mtr
3	Supply & installation of additional 3/4" copper piping and drain piping for the split air conditioners including all civil works complete	20	1Mtr
4	Supply & installation of pair of MS (Mild Steel) stand for outdoor unit, as per standard design available in the market	10	1 set
	TOTAL FOR AIR CONDITIONING WORK		

GST 28%

Total