

BOQ FOR CBOA DELHI OFFICE IN HALL (BACK SIDE) OF B/O BHAGIRATH PALACE.

S.No	Item Description	unit	qty (approx)	rate	amount
1	P/F Aluminium partition with powdered coated section of size 2.5"x1.5" with clear float glass of thickness 6mm. The item shall includes all vertical & horizonatal members/accessories required to make structure stable as per the satisfaction of Engineer-in-charge	sqft	140		
2	P/F Aluminium door with powdered coated section of size 2.5"x1.5" with clear float glass of thickness 6mm. The item shall includes all vertical & horizonatal members/accessories required to make structure stable as per the satisfaction of Engineer-in-charge. The item shall include handles, locks, door closure and other accessories etc.	sqft	21		
3	GRID FALSE CEILING /Modular False ceiling :Providing and fixing suspended false ceiling consisting : approved make MODULAR CEILING				
	Tile: Classic Lite RH 95;				
	Suspension system Suprafine 15 ()False ceiling will be measured on horizontal plane only. Horizontal plane measurements are to be inclusive of all vertical drops, edge mouldings, fascias, etc.Rate quoted to include all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect. Rate quoted to include cost of providing support framework formed of perimeter channels for fixing light fixtures, AC grills/diffusers etc. Also to provide concealed perimeter channel support as required to support modular grid ceiling sections at junction between gypboard false ceiling and modular grid tile ceiling.	sqft	80		

4	Providing wiring (supply, fixing, testing and comm. etc) for light point / Exhaust fan point / ceiling fan / door bell point/6A Switch-socket point etc with 2x1.5+1X1.5 sq mm FRLS PVC insulated copper conductor single core multi stranded wire in MMS grade-PVC conduit with conduit accessories like bend , junction box etc in concealed/surface manner as per site requirement with suitable Modular Switches with plate and metal / PVC box, ceiling rose , bulb holder etc including 1.5 sqmm PVC insulated copper earth wire etc complete as required. Wire colors : Red, Black, Green .Supplying, providing wiring (supply, fixing, testing and comm. etc) for circuit with 2 x 2.5 + 1 x 2.5 sq mm FRLS PVC insulated copper conductor single core multi stranded wire in MMS grade-PVC conduit with conduit accessories like bend, junction box etc on surface / recessed manner etc (Wiring from D.B. / Source to Board/destination) and making good all the damages, painting, cleaning the site etc complete as required as per site requirement and as directed. [LIGHT/6A switch/socket :(Maximum three points to be looped from primary); [3 nos. light point + 2 nos. 6A socket + 1 no. Fan point]; Brand - Polycab/RR Kabel	nos.	6		
5	P/F 1 x 25w LED Tube light (Philips/wipro/crompton)	nos.	3		
	TOTAL				