

निविदा दस्तावेज/TENDER DOCUMENT

FINANCIAL BID / वित्तीय बोली

Proposed Interior and allied Works at B/O PANVEL under Thane Region

(All Empanelled Vendors for Furniture Works Up to 25 Lakhs)



विज्ञापन की दिनांक/ Date of Advertisement	20-06-2022
प्रस्तुत करने की अंतिम दिनांक / Last Date of Submission	11-07-2022 15:00Hrs
खुलने की दिनांक Opening Date	11-07-2022 15:30 Hrs
कार्य अवधि/Time Period of Work	कार्य आदेश प्रदान करने की दिनांक से 30 दिन 30 days from award of Work Order
बयाना जमा राशि/Earnest Money Deposit	Rs.11, 500.00(Rupees Eleven Thousand Five Hundred Only) DD In favour of Central Bank Of India, Payable at Mumbai, MSME Registered Vendors are Exempted from EMD. Relevant Documents to be submitted in Technical Bid.
निविदा दस्तावेज का मूल्य/Cost of Tender Document(गैर वापसी योग्य/Non Refundable)	रु./Rs.1000.00 (सेन्ट्रल बैंक ऑफ इंडिया के पक्ष में मांग ड्राफ्ट जो मुंबई पर देय हो/ DD In favour of Central Bank Of India, Payable at Mumbai. Offers without Tender Cost will not be considered.
खुलने की दिनांक से निविदा की वैधता/Validity of Tender from the date of opening of Financial Bid.	90दिन/ days
प्रस्तुत किए जाने वाले दस्तावेज/ Documents to be provided	Only for Empanelled Vendors of Bank under Respective Category.
Independent External Monitor(IEM)	Mr Trivikram Nath Tiwari MAIL ID: - trivikramnt@yahoo.co.in Mr.Jagadip Narayan Singh MAIL ID: - jagadipsingh@yahoo.com
Email for Correspondence	gadthanro@centralbank.co.in archmmzo@centralbank.co.in
संपर्क व्यक्ति का नाम /Contact person name	Mr V.Amarnath –Manager, Architect.-6303929013 Mr. Kuldeep –Regional Security Officer-9322580709

प्रस्तुतकर्ता/SUBMITTED BY:

ठेकेदार का नाम/NAME OF CONTRACTOR :

पता/ADDRESS :

जीएसटी विवरण/GST DETAILS

Central Bank of India, Regional Office, Marathi Granth Sangralaya Building, Netaji Subhas Chandra Road, Thane-400601
Tel No: 022-25345721

Visit us at [http:// www.centralbankofindia.co.in](http://www.centralbankofindia.co.in)

सेनट्रल बैंक ऑफ इंडिया/ CENTRAL BANK OF INDIA

बिल ऑफ क्वांटिटि के लिए प्राक्कथन/PREAMBLE TO THE BILL OF QUANTITIES

प्रस्तावित कार्यालय परिसर में प्रस्तावित कार्य निविदा के आवरण पृष्ठ (पृष्ठ नं. निविदा के आवरण पृष्ठ (पृष्ठ संख्या 1) में उल्लेखानुसार करना होगा. प्रस्तावित कार्य की गुणवत्ता में सर्वश्रेष्ठ कारीगरी होना चाहिए। ठेकेदार को यह सुनिश्चित करना चाहिए कि प्रोजेक्ट के लिए सामग्री की सूची में उल्लिखित सामग्री श्रेष्ठ गुणवत्ता की हो।

The work proposed to be carried out at the proposed Office premises as mentioned on the cover page (page no.1) of the tender The quality of work proposed should have ***the best*** workmanship. The contractor should ensure that only the first quality materials mentioned in the list of material is purchased for the project.

1. कार्य इस तरह से किया जाए कि स्वरूप में कोई गड़बड़ न हो.

The work should be carried out in such a way that the structure is not disturbed.

2. निविदा प्रस्तुत करने से पहले विनिर्देशन में किसी भी अंतर/विसंगति को को प्रभारी इंजीनियर के साथ स्पष्ट किया जाना चाहिए। प्रभारी इंजीनियर को कार्य के दौरान मूल अवधारणा के अनुरूप एक उचित सीमा तक विनिर्देश को संशोधित करने की स्वतंत्रता होगी; निविदाकर्ता को ऐसा कार्य बिना अतिरिक्त लागत के करना होगा.

Any difference / discrepancies in the specification should be clarified with the Engineer in charge before submitting the tender. The Engineer in charge will have the liberty to modify the specification to a reasonable limit to suit the basic concept during the course of work; the tenderer should carry out such work without any extra cost.

3. किसी भी बड़े संशोधन के मामले में ऐसी वस्तुओं को अतिरिक्त मद के रूप में माना जाएगा. ऐसी मदों का भुगतान का इंजीनियरिंग दर / बाजार दर विश्लेषण के आधार पर किया जाएगा. सामग्री और श्रम की कुल लागत का 15% निविदाकर्ता के लाभ के रूप में माना जाएगा.

In case of any major modification such items will be considered as extra items. Payment for such items will be paid based on the Engineering rate / Market rate analysis. ***15% of the total cost of material and labour will be considered as tenderer's profit.***

4. ठेकेदार को सुचारु कार्य प्रवाह के लिए साइट पर नियुक्त अन्य ठेकेदार के साथ समन्वय करना होगा.

The contractor should co-ordinate with the other contractors employed at the site for smooth flow of work.

NOTE:

The Building is occupied by other Tenants. The work need to be carried out as per the instruction of the Bank time schedule. Further, the work needs to be carried in phase wise. The Contractor should prevent the external glazing and the flooring with plastic sheets and P.O.P. sheet respectively.

1. The contractor should obtain necessary permission from the Local Municipal Authorities any Government Authority if required along with the security deposit amount, the security amount will be reimbursed to the contractor.
2. The Contractor needs to clean the site on day to day basis.

BILL OF QUANTITIES:

Note:

1. Rates to be quoted by the tenderers in the item rate tender in figures and words shall be accurately filled in, so that there is no discrepancy in the rates written in figure and in words. However, if a discrepancy is found between the rate written in figures and rate written in words then the rate which correspond with the amount worked out by the contractor shall be taken as correct.
2. If the amount of an item is not worked out by the tendered, or it does not correspond with the rate written either figures or in words, then the rate quoted by the tenderer in words shall be taken as correct.
3. Where the rate quoted by the tenderer in figures and in words tally but the amount is not worked out correctly, the rate quoted by the contractor will be taken as correct, not the amount.
4. The work need to be carried out as per the time schedule instructed by Bank.
5. All other office furniture, office equipment, flooring, false ceiling etc. to be cover with plastic sheet or required packing materials
6. Any damages done by the contractor will be recovered from the contractors.
7. Cleaning to be done on day to day basis.
8. Electrician and one supervisor should be posted in working day to avoid any office disturbance and maintain the office smoothly.

सेनट्रल बैंक ऑफ इंडिया/ CENTRAL BANK OF INDIA

बिल ऑफ क्वांटिटि के लिए प्राक्कथन/PREAMBLE TO THE BILL OF QUANTITIES

प्रस्तावित कार्यालय परिसर में प्रस्तावित कार्य निविदा के आवरण पृष्ठ (पृष्ठ नं. निविदा के आवरण पृष्ठ (पृष्ठ संख्या 1) में उल्लेखानुसार करना होगा. परिसर में सज्जा, सिविल,इलेक्ट्रिकल और लेन केबलिंग कार्य उपलब्ध कराना प्रस्तावित है. प्रस्तावित कार्य की गुणवत्ता में सर्वश्रेष्ठ कारीगरी होना चाहिए। ठेकेदार को यह सुनिश्चित करना चाहिए कि प्रोजेक्ट के लिए सामग्री की सूची में उल्लिखित सामग्री श्रेष्ठ गुणवत्ता की हो.

The work proposed to be carried out at the proposed Office premises as mentioned on the cover page (page no.1) of the tender. The premise is proposed to be provided with Furnishing, civil, Electrical and LAN cabling works. The quality of work proposed should have **the best** workmanship. The contractor should ensure that only the first quality materials mentioned in the list of material is purchased for the project.

1. कार्य इस तरह से किया जाए कि स्वरूप में कोई गड़बड़ न हो.

The work should be carried out in such a way that the structure is not disturbed.

2. निविदा प्रस्तुत करने से पहले विनिर्देशन में किसी भी अंतर/विसंगति को को प्रभारी इंजीनियर के साथ स्पष्ट किया जाना चाहिए। प्रभारी इंजीनियर को कार्य के दौरान मूल अवधारणा के अनुरूप एक उचित सीमा तक विनिर्देश को संशोधित करने की स्वतंत्रता होगी; निविदाकर्ता को ऐसा कार्य बिना अतिरिक्त लागत के करना होगा.

Any difference / discrepancies in the specification should be clarified with the Engineer in charge before submitting the tender. The Engineer in charge will have the liberty to modify the specification to a reasonable limit to suit the basic concept during the course of work; the tenderer should carry out such work without any extra cost.

3. किसी भी बड़े संशोधन के मामले में ऐसी वस्तुओं को अतिरिक्त मद के रूप में माना जाएगा. ऐसी मदों का भुगतान का इंजीनियरिंग दर / बाजार दर विश्लेषण के आधार पर किया जाएगा. सामग्री और श्रम की कुल लागत का 15% निविदाकर्ता के लाभ के रूप में माना जाएगा.

In case of any major modification such items will be considered as extra items. Payment for such items will be paid based on the Engineering rate / Market rate analysis. 15% of *the total cost of material and labour* will be considered as *tenderer's profit*.

4. ठेकेदार को सुचारु कार्य प्रवाह के लिए साइट पर नियुक्त अन्य ठेकेदार के साथ समन्वय करना होगा.

The contractor should co-ordinate with the other contractors employed at the site for smooth flow of work.

SCHEDULE OF BILL OF QUANTITIES

NOTE : The quoted rate should be inclusive of materials, labour, wages, fixtures, transportation, installation, **all taxes (excluding GST)**, wastages, Octroi, machinery, temporary works such as scaffolding, cleaning, overheads, profit, statutory expenses, incidental charges and all related expenses to complete the work.

Sno	Description	Unit	Qty	Rate(Rs.)	Amount(Rs.)
PART A - LOOSE FURNITURE					
1	GENERAL :				
	All Tables / counters/ work stations to have 19mm Ply block board top & sides, and apron/front modesty 12 mm comm. Ply/board . Unless otherwise specified, all external/exposed surfaces shall be provided with 1.0 mm laminate finish and all internal surfaces shall be painted with white/ivory shade of satin finish enamel paint of approved make. Drawer units to be made from 12mm /19mm ply, with steam beach/teak wood lipping on edges . The drawers to run on telescopic drawer channels of approved make. Drawer units to have two smaller and one bigger drawers and locking arrangement (Godrej or equivalent). Foot-rest 75x50mm 2nd class cedar wood member to be fixed for each table the rate to include all hardware such as drawer channels, SS handles etc. The item also includes a tray for key board running on telescopic channel, finished with laminate on top and rounded front size 560x450 readymade EBCO make CPU trolley with castors etc. complete. In case of curved shape of table / counter, length at the centre of the top shall be measured for payment.				
1.1	B.M. 'S TABLE	Nos	01	20,000.00	20,000.00
	Providing and fixing Branch Manager Table as per main specification but finished in 1 mm laminate in two or more colours . The table size to be 5'-6" x 2'-6" x 2'-6" & storage unit 3'-0" x 2'-0". Table top to be provided with 6mm/8mm toughened Glass on SS Metal Studs.				
1.2	OFFICER'S TABLES	Nos	03	16,000.00	48,000.00
	Providing and fixing Officer/Manager Table as per main specification but finished in 1 mm laminate in two or more colours . Table Top to be provided with 6mm/8mm Toughened Glass on SS Metal Studs. The table size to be 4'-6" x 2'-6" x 2'-6" &				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

	storage unit 3'-0" x 1'-6"				
1.3	SWO Counter	RFT	5	5,000	25,000.00
	Providing and fixing SWO Table as per main specification but finished in 1 mm laminate in two or more colors The table front provided with laminate on S.S Studs (Size 135 x 60 mm aprox.). Counter items also includes Front modesty with 19mm Commercial ply with laminate. Drawer units to be as specified in MAIN specifications. BUT with divisions for currency as per BANK's instructions, The drawer units to have AUTOLOCKING system for drawers (Godrej). One footrest per occupant, key board tray 560x450 and CPU stand. All as per MAIN Specifications for tables. Inside of the counter & drawers shall be painted with satin finished enamel paint of approved make and ivory/white shade etc, complete to the satisfaction of Architect/Bank. The storage unit to comply to specifications as stated for officer tables. The table size to be 5'-0" x 3'-1" x 2'-6" & storage unit 3'-0" x 1'-6" . The counter shall have the Work top and counter top as per design similar to cash counter stated in item 4 with 300mm wide granite(basic rate of granite Rs.225) adhering to specifications as stated.				
1.4	Cash Counter	RFT	6	4,000.00	24,000.00
	Providing and placing in position Cash Counter Table made from 19mm Commercial ply/Block Board and with 1mm laminate finish, with overall height of 1050 mm for working counter at 750mm height made from 18mm pre-polished 300mm wide granite (basic rate of granite Rs.225) over 19 mm commercial ply/ block board. And customer counter at 1050 mm height made from 12mm thick beveled glass placed over 300mm high, 12mm theatrical, frosted toughened glass. Front modesty with 19mm Comm. Ply/Board finished in 1 mm laminate. The Counter to have drawer units same as mentioned in Main specifications of Tables above except the drawers to have divisions as per Bank's instructions. The counter to have 1 footrest per occupant. Item also includes a key-board tray & C.P.U. stand of EARL Bihari make Inside of the counter & drawers				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

	shall be painted with satin finished enamel paint of approved make and ivory/white shade etc., complete to the satisfaction of Architect/Bank. The table size to be 5'-3" x 3'-1" x 2'-6" & storage unit 3'-0" x 1'-6".				
1.5	GLASS RAILING	SQ.FT	100	500.00	50,000.00
	Providing and fixing 12mm Etched float glass (straight or bent as per shape given in plan) in front of Cash Cabins and SWO with metal clamps/D brackets /S.S. Studs or Wooden supports including cut-outs for passing currency as per details. The edges of the glass to be polished complete with necessary cutting the holes in shape properly, grinding & polishing. The glass may be fixed in vertical or inclined position as per given drawings.				
1.6	SERVER ROOM COUNTER	RFT	05	3,000.00	15,000.00
	Providing and fixing Server Table including drawer units with same specifications as main table. The table size to be 5'-6" x 2'-6" (Ref Layout plan) general specifications for tables to be adhered.				
2.0	STORAGE CUPBOARDS				
	GENERAL :				
	All storage cabinets/ low height cabinets/side racks shall have 19mm Ply/ block board for box, shelves and shutters and 6mm ply for back. Unless otherwise specified, all external/exposed surfaces shall be provided with 1.0 mm laminate finish of approved make and design and all internal surfaces shall be painted with white/ivory shade of satin finish enamel paint of approved make. All edges of ply/block board shall have 25x12mm teak wood/ steam beach lipping. The cabinet shall have self-closing hinges , (Godrej, Ebco, Hettich), SS handles, magnetic catchers, godrej /equivalent locks etc. complete - as/drawing details to the satisfaction of Architect. The front area of cabinet i.e. length x height shall be measured for payment.				
2.1	FULL HEIGHT CABINETS	Sq.FT	380	600.00	2,28,000.00
	Providing & fixing box fill height cupboards 400/450mm deep & height 2100/2400 mm as per main specifications mentioned above.				

2.2	LOW HEIGHT STORAGE	Sq.FT	60	600.00	36,000.00
	Providing & fixing low height cupboards 400/450mm deep & height 750/900 mm as per main specifications mentioned above.				
3	WRITING DESK	No's	01	10,000.00	10,000.00
	Providing and fixing writing desk, using 10 mm bevelled clear glass top over 19 mm ply base +1mm Laminate on all exposed surfaces of ply , with pigeon holes of 6"x6" to keep slips, approx. size 4'0" x 1'6" x 0"8" , to be fixed at 3'6" height				
4	DROP BOX/COMPLAINT BOX	No's	02	5,000.00	10,000.00
	Size 3'3"L X1'0"Wx 2'6' H , to be made from 19mm thick MR Grade plywood and finished with 1 mm thick laminate outside, with steam beach/teak wood border/lipping on exposed edges as per design and drawing and inside shall have enamel paint. The drop box will have 3 internal (vertical) divisions for Local, Out station and Credit card payment cheques etc. with 3 openable shutters on front with lock. Front / Top shall have 3 nos. 6" long x 1" wide slits to drop letter / cheque etc.				
5	NOTICE BOARD /BRAND WALL	Sq.FT	100	200.00	20,000.00
	Providing & fixing on partition/ walls soft pin-up board as per following specification. Core material of 10mm thick soft board finished with approved fabric. Framed with teak wood of section 2" x 1.5" , Approx. board size 4'x2'-6"				
6	VERTICAL BLINDS	Sq.ft	-	-	-
	Providing & fixing as per approved sample 100mm wide vertical fabric blinds complete with handing chain. Sliding and tilting system in drawn position. Fabric veins to overlap by minimum 10mm (every 1.0 metre running length to have at least 11 Nos. 100mm wide fabric veins). Length of the blinds as mentioned in drawings bottom end to be at least 12mm from horizontal surface. Fabric strip, as that of fabric vein, to be fixed on both sides of aluminum top channel . Lower ends of blind to be weighed down and tied with each other on both				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

	corners, with ball chains. Item to be complete in all respects including fixing with bracket on wall or partition with raw plugs.				
7	ROLLING SHUTTER BOX	Sq.ft	180	100.00	18,000.00
	Providing & Fixing Rolling Shutter box with 12mm ply finished with 1mm thick laminate of shade & brand as per drawing complete for the finished item of work.				
8	FROSTED FILM	Sq.ft	100	80	8000.00
	Providing and pasting frosted film (3M, Garware make) on glass work including Bank's logo as required & as directed by the architect.				
9	Vinyl Graphics and One Way Stickers	Sq.ft	100	150	15,000.00
	Supply and fixing of vinyl graphics on solid partitions/pained surface with required adhesives and cleansers. Finishing entrance wall and side walls made of glass with high resolution graphics pictorial graphics as per instructions.				
10	Misc-Shifting /Repairing of Old furniture				
a	Removing/repairing/Shifting and re-lamination of workstation tables from old premises to new premises Branch new premises with change of handle, lock and minor carpentry repair work wherever required. This work also includes installation, cutting, fixing as per layout plan complete	Nos	2	5,000.00	10,000.00
b	Removing, Repairing and shifting of existing tables .The work includes, un installation, shifting, transportation, installation, repairing of workstations /cash cabin (excluding partitions) from old premises to new premises. All the workstations shall be in fully functional conditions after shifting. No extra payment will made of repairing of damages before or during shifting.	NOs	2	5,000.00	10,000.0
c	Removing, repairing, re-lamination and shifting of existing backside storage. This work also includes providing and fixing of selves, shutters and all necessary hardware's like locks, handles etc. and painting insides.	Sq.ft	60	200.00	12,000.00

d	Shifting of Existing Chairs/customer chairs from Old Branch to New Branch.	L.S	1	5,000.00	5,000.00
TOTAL FOR PART A- LOOSE FURNITURE				5,64,000.00	
PART B – FIXED FURNITURE					
9	PARTITIONS/PANELLING	Unit	Qty	Rate(Rs.)	Amount(Rs.)
	GENERAL : For Partitions : All partitions shall have a frame work of saal / kail/chill wood size 50x35 or 50x50 mm at spacing not exceeding 600mm c/c in both directions as per requirement with 6mm ply on both faces including grooves, with / without 1mm thick laminate of approved make and design, up to 750/900/1200/1500/2100/2400mm height and clear transparent/frosted/etched glass of 5/9mm thickness shall be provided above the height of 750/900mm as per drawings and details . Vertical members for framing shall be continuous/ one piece i.e. without joint. The rate to include provision of extra frame work as necessary for skirting and making cut-outs for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduit as per drawings and directions of site Eng. / Architect. All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti-termite properties. The work also includes doors with door closers /flap doors as per requirements along with all locks (Godrej or equivalent) Handles, Hinges, stoppers etc. as per bank's architect instructions Measurement of height shall be taken from finished floor level up to the bottom level of false ceiling, In case of varying heights on either side of partition, average heights shall be considered. For panelling : All panelling shall have a frame work of saal / kail/chill wood size 50x25 or 50x35 mm at spacing not exceeding 600mm c/c in both directions as per requirement with 12mm ply on both faces including grooves, with / without 1mm thick laminate of approved make and design, up to 750/900/1200/1500/2100/2400mm height . Vertical members for framing shall be continuous/ one piece i.e. without joint. The rate to include				

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

	provision of extra frame work as necessary for skirting and making cut-outs for electrical switch plates, switch boxes, light fittings light etc, making provision for laying conduit as per drawings and directions of site Eng. / Architect. All wood frame work to be applied with 2 coats of fire retardant paint and 1 coat of wood preservative with anti-termite properties. The panelling may also include approx. 1'6" x2'6"size soft board/s with melamine polished steam beach/ teak wood border & fabric for display of notices etc.as shown in drawing . Measurement of height shall be taken from finished floor level up to the bottom level of false ceiling, In case of varying heights on either side of partition, average heights shall be considered.				
9.1	LOW HEIGHT PARTITIONS	SQ.FT	120	350.00	42,000.00
	Providing and fixing Low height partition from floor level up to the 1220 /1530mm as per main specifications mentioned above.1.0mm thick laminate of approved make and design to be fixed on both faces over 6mm thick ply. Partition to have a 75x20 mm th. melamine polished cedar/steam beach/teak wood moulding on top and side edges of partition.9 mm thick plain/ etched glass above 900 mm height in taper or curved shape as detailed shall be fixed with steam beach/ teak wood beading of 25x12 size., complete with polishing/paining the grooves as per design and to the satisfaction on Architect / Bank. The low height partitions shall include flap doors with required hardware and fittings. The partition shall also include apprx.2'0"x 1'6" size soft board/s with fabric for display of notices etc.as shown in drawing.				
9.2	PARTLY GLAZED PARTLY LAMINATED WOODEN PARTITION	SQ.FT	160	350.00	56,000.00
	Providing and fixing partly Glazed Partition partly laminated wooden as per main specifications mentioned above up to bottom of false ceiling. Item also includes 5mm clear transparent Etched Glass above 900 mm to 2100 mm fixed in 35x20 mm cedar/steam beach/teak wood beading fixed around opening finished with melamine matt finish polish. Rest of specifications same as MAIN specifications of Partitions. etc. complete to				

	the satisfactions of Architect/ Bank.				
9.3	FULL HEIGHT , BOTH SIDES LAMINATED	SQ.FT	300	350.00	1,05,000.00
	Providing and fixing wall panelling as per design & pattern with 50x25mm Kail/Saal wood frame at 2'-0" c/c in both directions with 12mm Commercial ply on top and finished with 1.0 mm laminate. Over the panelling 1'6" x2'6"size soft board/s with melamine polished steam beach/teak wood border of size as specified by the architect & fabric for display of notices etc.as shown in drawing. Also at top, middle and bottom level a decorative border of melamine polished, 100x25/75x25 size cedar / steam beech as per design and details shall be fixed.				
9.4	FULL HEIGHT 12MM THK. TOUGHEN GLASS PARTITION:	SQ.FT	112	350.00	39,200.00
	P/F 12 mm thick glass full height glass embedded in aluminum anodized sections all around for external facade glazing. Anodizing to be Natural Finish shade. (On special cases, subject to approval). (Frame work details as mentioned in item no. 9) The works includes fixing of glass with Top & Bottom surfaces with proper support/frame.				
9.5	Door (Incl. Floor Spring)	Sq.ft	112	500.00	56,000.00
	Providing and fixing glass door for entry with 3" X 3" beach frame wood work duly fixed with the partition/wall with hold fast duly polished. A white beach wood frame work size 6" X 2" as top and bottom rail with a decorative handle of 600mm of approved brand, floor spring, Locks, etc., all complete. 4" X 2" thick stiles to be fixed on the frame 3 sides. 12mm thick etched glass and Central bank logo frosted design with necessary and blasting/granular blasting to be provided and edge should be machine bevelled polished. The work to be completed as per design and specification of the Architect all complete. The wooden portion to be duly melamine polished as instructed by the architect. The door shall be inclusive of and fixed on floor spring of ISI approved make such as Godrej/Everest / Everite / Efficient Gadget etc. complete.				
9.6	Solid flush door	No's	02	9,000.00	18,000.00

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

	Providing and fixing – Solid flush door made out of 35mm with both side laminate finish with necessary fitting with door closer provision . All material is of approved brand. Size of door 900 x2100 Doors-Providing and fixing single leaf solid core flush door 40mm thick factory made, finished on both sides with 1.0mm thick laminate of approved shade as indicated in drawing. Shutter to be lipped on all sides with 12mm thick teak wood beading. Applicable hardware's to be considered for following doors according to requirement as per detailed drawings including below mentioned hardware- Door closers Ball bearing Hinges, SS foot operated Door stoppers Mortise Latch Lock / concealed dead locks Mortise Handle.				
9.7	PVC /Anti Static Vinyl Flooring in Strong Room/Server Room Respectively	Sq.ft	150	80.00	16,000.00
	Providing & laying blended marble anti-static vinyl tiles of Tuskar make with 1.0mm thick flooring of homogeneous in colour, design and as per manufacturer's specifications and pattern as per details given by Architects.				
9.8	MS COLLAPSIBLE GATE	Nos	1	35,000.00	35,000.00
	MS Collapsible Gate Single shutter made out of vertical double channels 20mm x 8mm x 3mm at maximum 125 mm apart when fully stretched as specified, braced with flat iron diagonals 12 mm x 6 mm as specified in the item. The top and bottom rails shall be of M.S. section 50mm x 50mm x 6 mm and 65mm x 10mm M.S flat with 50 mm dia rollers in every fourth double channel. Nos 8 Collapsible Gate and other accessories to be painted with 2 coats of Red oxide primer and 2 coats of Black Enamel paint.				
	SIZE : 2200 mm x 2100 mm when fully stretched				
TOTAL FOR PART B- FIXED FURNITURE				3,67,200.00	

PART C –PAINT WORKS

1	PAINT WORKS				
1.1	ACRYLIC EMULSION PAINT	Sq.ft	3500	20.00	70,000.00
	Painting two or more coats with acrylic emulsion paint of Asian (Royale),I.C.I.(Velvet Touch) brand , or equivalent to give an even shade, including one or more coats of lime/cement based putty and primer, on the walls of banking hall, manager's cabin, meeting room, server room etc. Surface to be cleaned, sanded, levelled and repaired, on old and new work.				
1.2	SYNTHETIC ENAMEL PAINT	Sq.ft	400	15.00	6,000.00
	Painting two or more coats with synthetic enamel paint of approved brand, shade & manufacture to give an even shade including one or more coats of putty and primer . Surface to be sand paper cleaned and prepared; on inside of rolling shutters, grills, etc., on walls/partitions/furniture as directed by the architect/bank.				
1.3	SYNTHETIC ENAMEL PAINT WITH LOGO	Sq.ft	600	25.00	15,000.00
	Painting two or more coats with synthetic enamel paint of approved brand, shade & manufacture to give an even shade including one or more coats of putty and primer. Surface to be sand paper cleaned and prepared; on outside of rolling shutters with design/ logo of CENTRAL BANK OF INDIA., painted as directed by the architect/bank.				
1.4	APEX PAINT OUTSIDE	Sq.ft	500	15.00	7,500.00
	Painting two or more coats with acrylic based exterior paint of approved brand & manufacture (apex or equivalent), with given color scheme to give an even shade including one or more coats of suitable putty and primer. Surface to be sand paper cleaned and prepared; on outside of building walls, as directed by the architect/bank.				
1.5	DISTEMPER PAINT	Sq.ft	200	15.00	3,000.00
	Painting three or more coats of dry distemper paint of approved brand & manufacture to give an even shade on old and new work.				
TOTAL FOR PART C- PAINTING WORKS				1,01,500.00	

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर

SIGNATURE OF TENDERER WITH RUBBER STAMP

1	PART D - FALSE CEILING				
1.1	PLAIN GYPBOARD FALSE CEILING WITH PAINTING	SQ.FT	400	120.00	48,000.00
	Providing and fixing suspended false ceiling consisting of 12.5mm thick Gypsum board (India Gypsum) suspended on GI framework. GI framework to consist of GI perimeter channels 0.55mm thick 20mm x 30mm along perimeter of false ceiling of ceiling, screw fixed to wall/partition with nylon sleeves and screws @ 600mm c/c. Suspending GI intermediate channels of size 0.9mm thick 45mm x 15mm from the soffit at max dist. 1220mm c/c with ceiling angle 0.55mm thick 25mm x 10mm fixed to soffit using proprietary supplied GI cleats and steel expansion fasteners. Boards to be finished with proprietary supplied jointing tape and jointing compound and sand papered to achieve a smooth and seamless finish and 2 coats of primer along with coats of Acrylic paint suitable for Gypsum board up to Bank's Satisfaction .Rate quoted to include vertical all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect.				
1.2	GYPSUM DROP CEILING	SQ.FT	200	80.00	16,000.00
	As per design with vertical drops and curves. Specification of item to as above to be adhered.				
1.3	GRID FALSE CEILING /Modular False ceiling	SQ.FT	600	90.00	54,000.00
	Providing and fixing suspended false ceiling consisting: approved make MODULAR CEILING Tile: Classic Lite RH 95 ; Suspension system Suprafine 15 () False ceiling will be measured on horizontal plane only. Horizontal plane measurements are to be inclusive of all vertical drops, edge mouldings, fascia's, etc. Rate quoted to include all cut-outs required for light fixtures, smoke detectors and other services cut-outs complete as directed by Architect. Rate quoted to include cost of providing support framework formed of perimeter channels for fixing light fixtures, AC grills/diffusers etc. Also to provide concealed perimeter channel support as required supporting modular grid ceiling sections at junction between gypboard false ceiling and modular grid tile ceiling.				

TOTAL FOR PART D FALSE CEILING

1,18,000.00

SUMMARY OF BILL OF QUANTITIES

SNO	DESCRIPTION	AMOUNT(Rs.)	
1	PART A –LOOSE FURNITURE	5,64,000.00	
2	PART B –FIXED FURNITURE	3,67,200.00	
3	PART C–PAINT WORKS	1,01,500.00	
4	PART D–FALSE CEILING	1,18,000.00	
5	TOTAL FOR INTERIOER WORKS	11,50,700.00	
		Percentage	Amount (Rs.)
6	PERCENTAGE ABOVE OR BELOW OF TOTAL AMOUNT	+/_	
FINAL AMOUNT (5 +/- 6)			

AMOUNT IN WORDS :

NOTE : The quoted rate should be inclusive of materials, labour, wages, fixtures, transportation, installation, **all taxes (excluding GST)**, wastages, Octroi, machinery, temporary works such as scaffolding, cleaning, overheads, profit, statutory expenses, incidental charges and all related expenses to complete the work.

रबर की मोहर सहित निविदाकर्ता के हस्ताक्षर
SIGNATURE OF TENDERER WITH RUBBER STAMP

Confirmation of Acceptance of Tender terms and conditions

(To be signed by the bidder and enclosed along with their offer in a separate envelope)

We have studied the terms and conditions of Tender Enquiry including General and Special terms and conditions, the specifications, lay-out drawings, Schedule of Quantities, Commercial terms and conditions, Approved Makes, etc.

We are accepting all terms and conditions of the Tender without any deviation.

Offer with any deviations from the Tender Enquiry are likely to be rejected.

We also understand that the order / s will be placed in the name of principals only and not in the name of their dealer/s. Our quotation is based on the above.

Date: _____

SIGNATURE OF TENDERER

WITH RUBBER STAMP

DECLARATION

I / We hereby declare that I / We have read and understood the Terms and Conditions of the contract, Specifications, Drawings, and Schedule of Quantities etc. and hereby agree to abide by them. In token thereof, I / We have signed below and at the end of the Schedule of Quantities, failing which the tender is liable to be rejected.

I / We understand that our Tender will not be considered if the rates for items are not written both in FIGURES and WORDS.

I / We hereby confirm that only the relevant entries asked for, have been made within the Tender documents issued to us. I / We also confirm that in the event of any entry in this Tender document other than the relevant entry or condition shall make this Tender invalid.

Date : _____

SIGNATURE OF TENDERER

WITH RUBBER STAMP