

<b>CLIENT : CENTRAL BANK OF INDIA,</b>	
<b>PROJECT: - PROPOSED AIR CONDITIONING WORKS OF CENTRAL BANK OF INDIA, RSETI, N</b>	
<b>ARCHITECT'S ESTIMATE- AIR CONDITIONING WORKS</b>	
<b>Sr.</b>	<b>Item / Descriptions</b>
<b>A</b>	<b>Part - A Machine</b>
	<b>NOTE</b>
<b>a</b>	<b>Standard 3 mtrs of refrigerant piping, cabling &amp; drain should be included in cost of machi</b>
<b>b</b>	<b>The purpose of measurement multiple run of refrigerant piping, cabling &amp; drain between</b>
1	Supply of Bluestar/Daikin/Hitachi/carrier make 3 star & above rated - 1.0 TR Highwall split type air conditioners with power saver rotary compressor (Copper Condensor Coil) & remote control etc. complete.
2	Supply of Bluestar/Daikin/Hitachi/carrier make 3 star & above rated - 2 TR Highwall split type air conditioners with power saver rotary compressor (Copper Condensor Coil) & remote control etc. complete.
<b>B</b>	<b>Part - B Installation Testing &amp; Commissioning</b>
1	Refrigerant piping:- supply installation of soft copper 22 gauge refrigerant piping, complete with fittings elbows supporting arrangement on walls etc.
1.1	1.0 TR Split ac (Copper Condensor Coil)
1.2	2 TR Split ac (Copper Condensor Coil)
2	<b>ELECTRICAL CABLING:</b> Providing & Laying control electrical cabling (3 core & 6 core).
2.1	1.0 TR Split ac (Copper Condensor Coil)
2.2	2 TR Split ac (Copper Condensor Coil)
3	<b>DRAIN PIPING:</b> Drain water pipings work out of PVC piping, fitting accessories, bend, elbows, 25mm dia
4	<b>FRAME WORK:</b> Supply,fabrication & installation of MS base frame for outdoor units complete with epoxy painting, vibration isolating pads, supporters, hangers, brackets with locking arrangement etc for OUD.
4.1	1.0 TR & 2 TR Split ac
5	<b>TESTING &amp; COMMISSIONING:</b> Testing & commissioning of air conditioner compresing indoor units & outdoor condensing unit with nitogen pressure testing, vacumising & Gas charging.
5.1	1.0 TR & 2 TR Split ac
6	Loading unloading with Transportation
7	Filling the cutouts/Holes in the walls with cement mortar & finish with plain cement plaster as directed by Architect.


			<b>DATE : 9/04/2022</b>
<b>MIMBLAK , AHMEDNAGAR</b>			
<b>Qty.</b>	<b>Unit</b>	<b>Rate (Rs.)</b>	<b>Amount (Rs.)</b>
<b>ne &amp; above will cost as per measurements. (In split indoor &amp; outdoor shall be considered as single</b>			
1	EACH		
3	EACH		
		<b>Total</b>	
		<b>Add GST 28%</b>	
		<b>Total</b>	
10	Mtr		
7	Mtr		
6	Mtr		
20	Mtr		
25	Mtr		
4	Nos		
4	Nos		
1	Nos		
	L.S.		
<b>Total Installation work Part -B Rs.</b>			
		<b>Add GST 18%</b>	
		<b>Total</b>	

