



FURNITURE ARRANGEMENT PLAN

PLAN SHOWING PROPOSED ELECTRICAL WORK LAYOUT FOR BANK PREMISES OF CENTRAL BANK OF INDIA, CHAPRASHIPURA BRANCH, AMRAVATI, TQ. & DIST. - AMRAVATI.

ASHISH V. JOSHI
ENGINEERS . PLANNERS . VALUERS
NAWATHE NAGAR, AMRAVATI

Name of Work : Providing & Erection of Electrification work of Central Bank of India, Chaparashipura, Amravati

ABSTRACT

Sr.No.	Item	Qty	Rate	Total
1.	Prov. Point wiring light fan bell wiring 1 sp. Mm. in casing fitting modular switch, anchor, make	40 No.		
2.	Prov. Switch socket on switch board	09 No.		
3.	Prov. Circuit wiring in casing caping 2 x 1.5 sq.mm. + 1.5 sq mm in lighting switch board	50 mtr.		
4.	Prov. Circuit wiring mains in casing caping 2 x 2.5 sq.mm. + 1 .5 sq.mm. (for power plug cooer, water cooler, printer etc.)	50 mtr.		
3.	Prov. Circuit wiring mains in casing caping 4x6 sq.mm. 6 2.5 sq.mm. (Meter to MCBDB)	9 mtr.		
6.	Prov. Circuit wiring mains in casing caping 2X6 sq.mm.+ 2.5 sq.mm. (AC supply and power)	60 mtr.		
7.	Prov. & Fixing Industrial Socket for AC 25 A.	4 No.		
8.	Prov. &. Fitting 5A Switch	50 No.		
9.	Prov. & Fitting of 5 A Socket	50 No.		
10.	Prov. & Fitting of 1 6 A. Switch Socket for Power & Water Cooler	2 No.		
11.	Prov. & Fitting Ding Dong Bell	1 No.		
12.	Prov. & Fixing selling Fan Hook & Pipe	3 No.		
13.	Prov. & Fixing Electronics Fan Regulator	6 No.		
14.	Prov. & Fixing of 63 A. TPN 415V. for main supply	1 No.		
15.	Prov. & Fixing 12 W. DB Single Door 3 Phase	1 No.		
16.	Prov. & Fixing 6W DB Single Phase UPS DB	1 No.		
17.	Prov. & Fixing 6A to 32A MCB	12 No.		
18.	Prov. & Fixing 40A, 2 Pole MCB	4 No.		
19.	Prov. & Fixing 4 Pole MCB 40A	2 No.		
20	Prov. & Fixing LED panel 12 W/15W/20W LED Tube light one year Warranty	31 No.		
21.	Earthing Cooper Plate type Solt Koyala & Etc.	2 No.		
22.	S/F PVC 25 mm pipe erecting and fitting	50 mtr.		
23.	S/F PVC Casing 32 mm erecting and fitting	30 mtr.		
24.	S/F flexible pipe 25 mm erecting and fitting	20 Ft.		
25.	S/F Cat 6 Cable erecting and fitting	450 Ft.		
26.	S/F I/O Box RJ 45 Information outlet box fitting	11 No.		
27.	Dismantling switch rack remove and fitting	1 Job		
28.	Supply & Installation of 1.5 Ton AC Make LG & Other	4 No.		
		Total		

Material make Anchor Penta Modular, wire Anchor, Polycab make.