



NOTES:

- 1) SEPARATE LADIES & GENTS TOILETS SHALL BE COMPLETED BY OWNER IN ALL RESPECTS INCLUDING FLOOR/WALL TILES & SANITARY FIXTURES.
- 2) PHYSICALLY CHALLENGED RAMP (SLOPE 1:12) TO BE PROVIDED FOR BANK/ ATM ENTRY BY OWNER.
- 3) 2'X2' 'KAJARIA' MAKE VITRIFIED FLOOR TILES (AGCNL-K6211) OR SAME MATCHING SHADE IN NITCO/ JOHNSON MAKE IN BANKING HALL.
- 4) WINDOWS/ VENTILATORS SHALL BE PROVIDED WITH M.S. GRILL (12MM SQUARE BARS WELDED IN 3"X3" SQUARE MESH PATTERN).
- 5) FOR PANTRY GRANITE SLAB, CERAMIC WALL TILES WITH SINK & WATER TAPS IS TO BE PROVIDED BY LANDLORD.
- 6) 4 1/2" THK. BRICK WORK FOR RECORD ROOM, STATIONARY ROOM & UPS/ SERVER ROOM WITH PLASTER IS TO BE DONE BY LANDLORD
- 7) AFTER COMPLETION OF FURNITURE WORK LANDLORD HAVE TO DO THE FINAL PAINTING WITH PUTTY ON WALL/ CEILING/ COLUMNS ETC AS PER BANK'S BRANDING/ SATISFACTION.
- 8) M.S. ROLLING SHUTTER (IS 6248-1979) WITH KHADKA (GROUND EMBEDDING) LOCK & M.S. COLLAPSIBLE GATE (IS 10521-1983) OF REQUIRED SIZE FOR BRANCH ENTRY AND M.S. ROLLING SHUTTER FOR ATM OF REQUIRED SIZE TO BE PROVIDED BY OWNER AS PER BANK/ BRI SPECIFICATIONS.
9. CROSS VERIFY THE DIMENSIONS BEFORE STARTING OF WORK, IF ANY DISCREPANCY IS OBSERVED AT SITE, SHALL BE BROUGHT TO NOTICE OF ARCHITECT.

PROPOSED FURNITURE PLAN DEORIA MAIN BRANCH